


EACH LOT TO HAVE ONE
TREE TO BE LOCATED
EACH LOT TO HAVE ONE
BUILDER FROM LIST

*Property line (irrigation system
to be installed north
of the property line)

"LILAC WALK" BETWEEN
COMMON LILAC-4
SYRINGA VULGARI
SHRUBS TO BE PLANTED



LANDSCAPE NOTE

- The Landscape Contractor shall visit the project site prior to commencing work.
- All rough and finish grading to be performed by the Landscape Contractor shall verify at the project site prior to commencing work.
- No plant material shall be installed until construction has been completed in the area.
- All plant material shall meet the standards of the American Association of Nursery Stock.
- All container material to be grown in the minimum of six (6) months prior to planting.
- Deciduous and conifer trees will not be planted under conifer trees will extend 6' from the canopy. Mulch under deciduous trees 1.5 feet from the trees' trunk.
- Commercial grade poly lawn edging shall surround all planting beds in sodded areas.
- Three inches of wood mulch shall be installed around all shrubs and trees that are isolated from plants. Mulch under shrub beds will be contained under conifer trees will extend 6' from the canopy. Mulch under deciduous trees 1.5 feet from the trees' trunk.
- The Landscape Contractor shall repair all damage caused by the planting operation to the owner.

MONUMENT LOCATION
(TO BE DESIGNED BY OTHERS)

Irrigation Service
behind monument
PRINTED

Harveston Tree Service Company Ltd.

JAN 0, 2000